

Barringer & Barringer, Inc.

Landscape Services

AERATION AND SEEDING FOLLOW UP INSTRUCTIONS

The **first half** of the aeration and seeding process on your property is complete. For the next ten days to two weeks, new seedlings will germinate and root in.

As part of our weekly visit to your property, we assess the germination progress. We have spot seeded additional areas as needed. We perform other contracted services, but do not mow until sure that the new grass is rooted sufficiently. The existing grass looks a little tall during this time, but it is necessary.

The **second half** of this process is crucial. Proper watering is necessary to insure good seed germination. If you have irrigation, the controller has been set to cover areas properly.

For areas not covered by irrigation or if you do not have irrigation, please follow these necessary and important steps:

- **Keep lawn areas consistently moist (at least one inch of water per week).**
- **Light frequent sprinklings several times a day.**
- **Avoid puddling on the seed bed.**
- **Deep watering once or twice weekly is recommended after the seed has germinated.**
- **In the absence of rain, please be aware when the ground becomes too dry and water appropriately.**

The success of aeration and seeding is your commitment to water! We partner with you to develop a beautiful lawn and appreciate your help in this important process.